



05.07.2021

Installation of the roof on the first propane tank at the Handling and Storage Terminal

The assembly of the roof on the first propane tank has been completed. A lift weighing 290 tons, was lifted by forcing air under the dome with a slight overpressure of +0.02 bar. For safety reasons, the maximum speed of lifting the roof was 30 cm per minute.

Two cryogenic propane tanks are built at the Handling and Storage Terminal, which will be stored in a liquid state at a temperature of -42 degrees Celsius. The total capacity of each propane tank will be 40,000 m³. It is planned that the terminal will reload for the project 500 thousand tons of propane per year.

